


Super FRS Hot Cell Layout & remote handling in the Super FRS Hot Cell



- ❖ **Super FRS hot cell Overview**
- ❖ **Remote handling components**
- ❖ **Remote handling Processes**

The super FRS facility



Activation of the super FRS target components



Operation foreseen for the Super

FRS facility:

- 90 days run
- 120 days break

Isotope	Aktivität (A) Bq	Freigrenze (F) Bq	A / F ---	Halbwertszeit d
⁵⁴ Mn	1,65E+13	1,00E+06	1,65E+07	312,27
⁵¹ Cr	1,40E+13	1,00E+07	1,40E+06	27,7
⁵⁵ Fe	1,30E+13	1,00E+06	1,30E+07	996,41
⁵² Mn	6,14E+12	1,00E+05	6,14E+07	5,59
⁴⁸ V	5,06E+12	1,00E+05	5,06E+07	15,97

Table shows the activation of the main isotopes which are responsible for the activation of the components

3 days		120 days	
Bq	mSv/h	Bq	mSv/h
1,40E+11	9,00E-01	4,87E+10	1,96E-01

graphite target wheel

3 days		120 days	
Bq	mSv/h	Bq	mSv/h
1,35E+11	9,93E+00	5,10E+10	1,89E+00

target plug shielding

3 days		120 days	
Bq	mSv/h	Bq	mSv/h
2,54E+13	2,52E+03	1,17E+13	5,64E+02


Graphite absorber

3 days		120 days	
Bq	mSv/h	Bq	mSv/h
4,44E+12	3,69E+02	2,67E+12	1,24E+02


Cu-absorber



List of the components after a worst case scenario of 180 days beam time with U-238 and intensity of 1E+12 Ions/s and energy of 1,5GeV/u and then 120 days break. The table shows the activation of the parts after 3 and 120 days of decay. These parts are stored in 200l barrels in the floor of the decay cell.

Super FRS target area overview



The components will be moved in the shielding flask from the beam line to the hot cell and be inserted through the double lid slider of roof






The equipment of the HC



The main manipulation tools:

- 2 Gettinge MT200 Master-slave manipulators
- Power manipulator Wälischmiller A1000
- Plug turntable
- Saw / Hydraulic Scissors
- Lifter
- Waste barrel convey with double lid gate
- Funnel drawer
- General purpose small tools



Master slave and power manipulators



Photo: Wällischmiller


Getting MT200 Technical Specs

- Max load capacity: 20daN
- Max tongs force: 22daN
- Max tongs opening: 90mm
- Total length extracted: E+F+Z: 3270mm
- Detachable gripper and tongs
- Booting on slave side




Wällischmiller A1000 Technical Specs


- Max load capacity: 200 daN
- Max crane load capacity: 2 Tonnes
- Force feedback
- 6 axis movement
- Radiation resistance: 1MGy



Super FRS target beam line



The target chamber components



The target plug


Tasks regarding the target plug in the HC

Service yearly	Failure	Optional
Target wheel	Cooling plate	Target ladder
Stepper motor	Linear sleigh	
	Cooling hoses	

Target/ Striper ladder



Stepper motor

Target wheel




Target plug tasks


Step 1: cooling plate removal




Step 2:
release the quick
lock mechanism



Step 3:
removal of the
graphite target





Step 4:
separation of the
materials means
a crusher above
the double lid
barrel docking
station



Tasks on the detector plugs


Tasks in the HC concerning the detector plug

Service	Failure	Optional
	Mirror exchange	Target ladder
	Cooling plate exchange	
	Detector exchange	
	CV DD	
	IC	
	SEM Grid	
	Seetram	





Mirror

Diamond detector



SEM Grid


Tasks on the beam catcher plug








Beam catchers tasks in the HC

Service	Failure	Optional
Lower C-Absorber	Absorber frame	
Upper C-Absorber	Cooling hoses	
	Linear drive	
	Stepper Motor	

The plugs turntable and the realisation of the BC tasks





1. Dismounting of the lower graphite absorber
2. Dismounting of the upper graphite absorber
3. removal of the absorber C-frame
4. Removal of the linear drive



Pillow-seal plugs

Pillow seals Tasks in the HC

Service	Failure
	Pillow seal module
	Vacuum / compressed air pipes module

Plugs dimensions

Total height: 4m
Width: -1760mm
Length: 120mm
Weight: up to 2 tonnes



Antiprotons P-bar target & horn

P-bar Tasks in the HC

Service/3 months





Target disposing

Horn disposing

Antiproton Target and horn are not foreseen to be maintained. After they are inserted in the hot cell they will be cut by a saw or a hydraulic scissors and will be disposed. They are main waste volume which are in the 200l barrels

Horn cage
mechanical
interface of
the horn

Horn
Connector



Main Remaining tasks

❖ Hot cell utilities

- Layout and later installation of electrical network, monitoring, compressed air, environmental sensors
- Design and layout of tools in the hot cell

❖ Hot cell DMU model and 3D modeling of the tasks

❖ Turntable detailed design and manufacturing

❖ Design / manufacturing of the double lid shielding flask interface

❖ Design / manufacturing of the waste barrel convey

❖ Activation measurement station of the decay cell

❖ Documentation and approval of the authorities

Thank you for your attention